



PLANTING NOTES

- DO NOT SCALE FROM DRAWINGS.
- CONTRACTOR SHALL REPORT ANY DISCREPANCIES BETWEEN THE DRAWINGS AND THE FIELD CONDITIONS TO THE LANDSCAPE ARCHITECT PRIOR TO PLANTING. QUANTITIES REPRESENTED ON THE DRAWING PLANT LABELS SHALL SUPERCEDE THOSE ON THE PLANT LIST.
- NO SUBSTITUTIONS WILL BE ALLOWED WITHOUT PRIOR APPROVAL BY THE LANDSCAPE ARCHITECT AND/OR OWNER.
- ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN UNLESS OTHERWISE NOTED ON THE PLANT LIST.
- ALL PLANTS SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT AND/OR OWNER PRIOR TO THEIR INSTALLATION.
- ANY PLANTS LABELED 'SPECIMEN' ON THE PLANT LIST SHALL BE TAGGED AT SOURCE BY THE LANDSCAPE ARCHITECT AND/OR OWNER UNLESS DIRECTED OTHERWISE.
- THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING ABOVE AND BELOW GRADE UTILITIES AND SERVICES AND SHALL PROVIDE APPROPRIATE PROTECTIONS DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING THE LOCAL UTILITY LOCATION SERVICE PROVIDER PRIOR TO COMMENCING WORK. ANY UTILITIES DAMAGED DURING SITE WORK SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL POSITION ALL PLANT MATERIAL IN LOCATIONS SHOWN ON THE PLAN FOR REVIEW BY LANDSCAPE ARCHITECT AND/OR OWNER. THE CONTRACTOR IS RESPONSIBLE FOR ADJUSTING THE PLANTS AS NEEDED TO ACCOMMODATE FOR LEDGE AND SHALL CONTACT THE LANDSCAPE ARCHITECT IF PLANTING IS IMPEDED BY LEDGE.
- THE CONTRACTOR SHALL COORDINATE WITH THE LANDSCAPE ARCHITECT AND OWNER PRIOR TO BEGINNING SITE WORK TO DETERMINE THE PLANTING SOIL AMENDMENTS REQUIRED - SUCH AS THE ADDITION OF COMPOST AND/OR PEAT MOSS. UNLESS OTHERWISE DIRECTED, THE CONTRACTOR SHALL PROVIDE THE FOLLOWING GENERALLY ACCEPTED SOIL BACKFILL RATIO: 1/3 NATIVE SOIL, 1/3 IMPORTED LOAM, 1/3 COMPOST/PEAT MOSS. INITIALLY, THE CONTRACTOR SHALL ASSUME THE INCORPORATION OF 1-2 CUBIC YARDS OF COMPOST/PEAT MOSS PER 1000 SQUARE FEET OF PLANT BED. IN ADDITION, THE CONTRACTOR SHALL INCORPORATE A PLANT STARTER FERTILIZER SUCH AS 10-10-10 IN THE PLANTING SOIL MIX.
- THE CONTRACTOR SHALL REVIEW AND ADDITIONAL SITE DRAINAGE REQUIREMENTS WITH THE OWNER AND/OR LANDSCAPE ARCHITECT AND COORDINATE POTENTIAL IMPROVEMENTS IN ORDER TO ATTAIN POSITIVE DRAINAGE IN ALL CONDITIONS.
- THE CONTRACTOR SHALL INSTALL SHREDDED HARDWOOD BARK MULCH, SUCH AS PINE BARK MULCH THAT IS MEDIUM TO DARK BROWN IN COLOR AND FREE OF ANY DEBRIS OR LARGE PIECES OF WOOD. MULCHES WITH DYES WILL NOT BE ACCEPTED. MULCH ALL PLANT BEDS AFTER PLANTING TO THE FOLLOWING 'LOOSE MEASURE' DEPTHS:
 - TREES AND SHRUBS - 3"
 - PERENNIAL, GROUND COVER AND ORNAMENTAL GRASS BEDS - 1.5"
- THE CONTRACTOR IS RESPONSIBLE FOR SEEDING OR SODDING ALL AREAS DISTURBED DURING CONSTRUCTION ACCORDING TO THE PLANTING PLAN OR AS DIRECTED BY THE LANDSCAPE ARCHITECT AND/OR OWNER.
- EXISTING TREES TO REMAIN SHALL BE PROTECTED DURING CONSTRUCTION. THERE SHALL BE NO PARKING OR STOCKPILING OF CONSTRUCTION MATERIAL WITHIN THE DRIP LINE OF THE TREES TO REMAIN.
- THE CONTRACTOR SHALL MAINTAIN ALL PLANT MATERIAL UNTIL PROVISIONAL ACCEPTANCE OF THE PROJECT IS ISSUED BY THE LANDSCAPE ARCHITECT. ALL PLANTS SHALL BE GUARANTEED TO BE ALIVE AND IN VIGOROUS GROWING CONDITION FOR A PERIOD OF ONE (1) FULL YEAR FROM THE TIME OF PROVISIONAL ACCEPTANCE. FINAL ACCEPTANCE WILL BE MADE BY THE LANDSCAPE ARCHITECT AND OWNER AT THE END OF THE GUARANTEE PERIOD. ANY PLANTS DEEMED UNACCEPTABLE PRIOR TO THE END OF THE GUARANTEE PERIOD SHALL BE PROMPTLY REPLACED AT THE CONTRACTOR'S EXPENSE.
- THE CONTRACTOR SHALL UPDATE THE EXISTING IRRIGATION SYSTEM TO IRRIGATE ALL PLANTING BEDS AND LAWN AREAS. THE CONTRACTOR SHALL COORDINATE WITH THE LANDSCAPE ARCHITECT IN THE DEVELOPMENT OF THE SYSTEM. THE CONTRACTOR SHALL REVIEW THE CONNECTION OF THE SYSTEM TO DOMESTIC WATER SOURCE OR WELL WATER WITH GENERAL CONTRACTOR/OWNER. THE CONTRACTOR SHALL PROVIDE ALL EQUIPMENT, CONTROLLERS, TIMER, OPERATIONAL INSTRUCTIONS, WARRANTY, AS BUILT DRAWINGS AND FIRST YEAR SYSTEM SERVICE.

PLANT LIST

SYM	QTY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
EVERGREEN TREES					
IO	9	Ilex opaca	American Holly	6'/7' ht.	B&B
SHRUBS					
CA	10	Clethra alnifolia	Sweet Pepperbush	#5	CONT. or B&B
IG	13	Ilex glabra	Inkberry	#10	CONT. or B&B
VD	1	Viburnum dentatum	Arrowwood Viburnum	#7	CONT. or B&B

FENCING LEGEND

- FENCE TYPE A***
 6' HT VERTICAL CEDAR BOARD
 FENCE WITH PICKET TOPPER
 (BLEACHING OIL FINISH)
 56 LF
 (1) 6' DOUBLE GATE
- FENCE TYPE B***
 POOL ENCLOSURE FENCE 42" -
 48" HT. HORIZONTAL CEDAR
 BOARD FENCE (SPACED)
 63 LF
 (2) 4' SINGLE SELF LATCH GATE

LIGHTING LEGEND

SYMBOL	FIXTURE TYPE	QTY	MODEL	LAMP	WATTAGE	VOLTAGE	FINISH
	PATH LIGHT	8	FX Luminaire - PF Path Light	LED	1.6W	- 12V -	Natural

- ALL FIXTURES BY AURORA LIGHTING, FX LUMINAIRES, CAST LANDSCAPE LIGHTING OR APPROVED EQUAL. CONTRACTOR SHALL SUBMIT SUBSTITUTION OPTIONS TO THE LIGHTING CONSULTANT AND LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO INSTALLATION.
- CONTRACTOR SHALL COORDINATE LAMP SELECTION AND OPTIONS WITH LIGHTING CONSULTANT AND LANDSCAPE ARCHITECT TO ACHIEVE APPROPRIATE LIGHT COVERAGE.
- IF REQUESTED, THE CONTRACTOR SHALL CONDUCT A LIGHTING MOCK-UP SESSION WITH THE DESIGN TEAM AND OWNER TO VERIFY FINAL LIGHTING NEEDS PRIOR TO PURCHASING AND INSTALLATION, AND TO REVIEW POTENTIAL TRANSFORMER AND CONTROLLER LOCATIONS.
- CONTRACTOR SHALL SUPPLY ALL FIXTURES, LAMPS/BULBS, WIRING, CONTROLLERS, TRANSFORMERS, TIME CLOCKS, PHOTOCELLS, OPERATIONAL INSTRUCTIONS, WARRANTIES, AND AS-BUILT DRAWING.

LANDSCAPE PLAN

4 ROSE HILL LANE
 CHASSET, MA

SEAN PAPICH
 landscape architecture

222 north street
 7781.741.5455
 hingham.ma 02043
 www.seanpapich.com

DATE: JAN. 27, 2022
 rev. APR. 13, 2022

SCALE: 1/8" = 1'-0"

PROJECT NO. 2135

